



Element Materials Technology, Unit 1, North Luton Industrial Estate, Sedgewick Road, Luton, Bedfordshire, LU4 9DT  
Your Element Contact: Paul Martin (07827 332 630)  
E: paul.martin@element.com

**Stack Emissions Testing Report Commissioned by**  
Sundown Products Ltd

**Installation Name & Address**

Sundown Products Ltd  
Chipping Plant  
Station Road  
Tilbrook  
Huntingdon  
PE28 3PA

PPC Permit: B02/06

**Stack Reference**

S2 - Cooler Plant

**Dates of the Monitoring Campaign**

4th July 2019

**Job Reference Number**

ELU-0319

**Report Written by**

Neil Teixeira  
Team Leader  
MCERTS Level 2  
MM 05 583  
TE1 TE2 TE3 TE4

**Report Approved by**

Phil Soley  
Deputy Regional Manager  
MCERTS Level 2  
MM 12 1187  
TE1 TE2 TE3 TE4


**Report Date**

16th September 2019

**Version**

Version 2

**Signature of Report Approver**



## CONTENTS

TITLE PAGE

CONTENTS

EXECUTIVE SUMMARY

Monitoring Objectives	3
Monitoring Results	4
Monitoring Dates & Times	5
Process Details	6
Monitoring & Analytical Methods	7
Summary of Sampling Deviations	7
Sampling Location	8
Plant Photos / Sample Points	9

APPENDIX 1 - Monitoring Personnel & List of Equipment

APPENDIX 2 - Raw Data, Sampling Equations & Charts

*Opinions and interpretations expressed herein are outside the scope of Element's ISO 17025 accreditation.*

*This test report shall not be reproduced, except in full, without the written approval of Element.*

*This version of the test report supersedes the previous version of the test report. Please destroy all previous versions to ensure no confusion arises from having multiple test reports in existence.*

## Executive Summary

(Page 1 of 7)

### MONITORING OBJECTIVES

Sundown Products Ltd, Tilbrook  
S2 - Cooler Plant  
4th July 2019

#### Overall Aim of the Monitoring Campaign

Element were commissioned by Sundown Products Ltd to carry out stack emissions testing on the S2 - Cooler Plant at Tilbrook.

The aim of the monitoring campaign was to demonstrate compliance with a set of emission limit values (ELVs) as specified in the Site's Permit.

#### Special Requirements

There were no special requirements.

#### Target Parameters

Total Particulate Matter

## Executive Summary

(Page 2 of 7)

### MONITORING RESULTS

Sundown Products Ltd, Tilbrook

S2 - Cooler Plant

4th July 2019

where MU = Measurement Uncertainty associated with the Result

Parameter	Concentration				Mass Emission			
	Units	Result	MU +/-	Limit	Units	Result	MU +/-	Limit
Total Particulate Matter <sup>1</sup>	mg/m <sup>3</sup>	26.6	2.7	150	g/hr	671	74.9	-
Water Vapour	% v/v	0.50	0.058					
Stack Gas Temperature	°C	31.9						
Stack Gas Velocity	m/s	10.0	0.14					
Volumetric Flow Rate (ACTUAL)	m <sup>3</sup> /hr	28236	1341					
Volumetric Flow Rate (REF)	m <sup>3</sup> /hr	25267	1200					

NOTE: VOLUMETRIC FLOW RATE & VELOCITY DATA TAKEN FROM THE PRELIMINARY VELOCITY TRAVERSE.

<sup>1</sup> Reference Conditions (REF) are: 273K, 101.3kPa, without correction for water vapour content.

## Executive Summary

(Page 3 of 7)

### MONITORING DATE(S) & TIMES

Sundown Products Ltd, Tilbrook

S2 - Cooler Plant

4th July 2019

Parameter		Units	Concentration	Units	Mass Emission	Sampling Date(s)	Sampling Times	Duration mins
Total Particulate Matter	R1	mg/m <sup>3</sup>	26.6	g/hr	671	04/07/2019	14:00 - 14:32	32
Velocity Traverse	R1					04/07/2019	13:35 - 13:55	

All results are expressed at the respective reference conditions.

## Executive Summary

(Page 4 of 7)

### PROCESS DETAILS

Sundown Products Ltd, Tilbrook

S2 - Cooler Plant

4th July 2019

#### Standard Operating Conditions

Parameter	Value
Process Status	Operational
Capacity (of 100%) and Tonnes / Hour	-
Continuous or Batch Process	Continuous Batch
Feedstock (if applicable)	Animal Bedding
Abatement System	Cyclone
Abatement System Running Status	Operational
Fuel	N/A
Plume Appearance	None Visible

## Executive Summary

(Page 5 of 7)

### MONITORING & ANALYTICAL METHODS

Sundown Products Ltd, Tilbrook

S2 - Cooler Plant

4th July 2019

Parameter	Monitoring				Analysis				MCERTS Testing	LOD (Average)
	Standard	Technical Procedure	ISO 17025 Testing	Testing Lab	Analytical Procedure	Analytical Technique	ISO 17025 Analysis	Analysis Lab		
Total Particulate Matter	EN 13284-1	CAT-TP-01	Yes	EET	CAT-TP-03	Gravimetric	Yes	EET	Yes	0.3 mg/m <sup>3</sup>
Water Vapour	EN 14790	CAT-TP-05	Yes	EET	CAT-TP-05	Gravimetric	Yes	EET	Yes	0.1 % v/v
Velocity & Vol. Flow Rate	EN 16911-1 (MID)	CAT-TP-41	Yes	EET	Pitot Tube and Thermocouple				Yes	1.2 m/s

### ANALYSIS LABORATORIES

(with short name reference as appears in the table above)

Element Stockport (EET)	ISO 17025 Accreditation Number: 4279
-------------------------	--------------------------------------

### SUMMARY OF SAMPLING DEVIATIONS

Parameter	Run	Deviation
Total Particulate Matter	1	Only one out of two required sampling lines was available, however the number of sample points used on the available line were increased to the minimum required by the Standard
		The sample points where the angle of swirl was > 15° were omitted from the sampling exercise. The effective number of points was doubled and any non-compliant swirl

## Executive Summary

(Page 6 of 7)

### SUITABILITY OF SAMPLING LOCATION

#### Duct Characteristics

Parameter	Units	Value
Type	-	Circular
Depth	m	1.00
Width	m	-
Area	m <sup>2</sup>	0.79
Port Depth	cm	10
Orientation of Duct	-	Vertical
Number of Ports	-	1
Sample Port Size	-	4" BSP

#### Location of Sampling Platform

General Platform Information	Value
Permanent / Temporary Platform	Permanent
Inside / Outside	Inside

#### Platform Details

EA Technical Guidance Note M1 / EN 15259 Platform Requirements	Value
Sufficient working area to manipulate probe and operate the measuring instruments	No
Platform has 2 levels of handrails (approx. 0.5m & 1.0m high)	Yes
Platform has vertical base boards (approx. 0.25m high)	Yes
Platform has chains / self closing gates at top of ladders	Yes
There are no obstructions present which hamper insertion of sampling equipment	No
Safe Access Available	Yes
Easy Access Available	Yes

#### Sampling Location / Platform Improvement Recommendations

All platforms should be designed in accordance with the requirements in the Environment Agency's Technical Guidance Note M1 and EN 15259.

#### EN 15259 Homogeneity Test Requirements

There is no requirement to perform a EN 15259 Homogeneity Test on this Stack.

#### Sampling Plane Validation Criteria (from EN 15259)

Criteria in EN 15259	Units	Traverse 1	Required	Compliant
Lowest Differential Pressure	Pa	22.0	> 5 Pa	Yes
Mean Velocity	m/s	9.99	-	-
Lowest Gas Velocity	m/s	5.26	-	-
Highest Gas Velocity	m/s	13.97	-	-
Ratio of Above	: 1	2.65	< 3 : 1	Yes
Maximum Angle of Swirl	°	46.00	< 15°	No
No Local Negative Flow	-	Yes	-	Yes



## Executive Summary

(Page 7 of 7)

### PLANT PHOTOS


Photo 1



Photo 2



### SAMPLE POINTS



where

- = isokinetic point sampled at
- = isokinetic point not sampled at
- = combustion gases sample point
- = non-isokinetic sample point

## APPENDICES

### APPENDIX CONTENTS

APPENDIX 1 - Stack Emissions Monitoring Personnel, List of Equipment & Methods and Technical Procedures Used

APPENDIX 2 - Summaries, Calculations, Raw Data and Charts

# APPENDIX 1

## STACK EMISSIONS MONITORING PERSONNEL

Position	Name	MCERTS Accreditation	MCERTS Number	Technical Endorsements
Team Leader	Neil Teixeira	MCERTS Level 2	MM 05 583	TE1 TE2 TE3 TE4
Trainee	Dan Croxford	MCERTS Trainee	MM 19 1539	None

## LIST OF EQUIPMENT

Extractive Sampling		Instrumental Analysers		Miscellaneous Items	
Equipment Type	Equipment I.D.	Equipment Type	Equipment I.D.	Equipment Type	Equipment I.D.
Control Box DGM (1)	CAT 7.101	Horiba PG-250	-	Digital Manometer (1)	CAT 3.232
Control Box DGM (2)	-	Horiba PG-250	-	Digital Manometer (2)	-
Box Thermocouples (1)	CAT 3.205	Servomex 4900	-	Digital Temperature Meter	CAT 3.232
Box Thermocouples (2)	-	Eco Physics CLD 822Mh	-	Stopwatch	CAT 14.53
Umbilical (1)	CAT 3.205	ABB AO2020-URAS26	-	Barometer	CAT 13.51
Umbilical (2)	-	Servomex 5200MP	-	Stack Thermocouple (1)	-
Oven Box (1)	-	JCT JCC P1 Cooler	-	Stack Thermocouple (2)	CAT 4.1164
Oven Box (2)	-	Gasmet DX4000	-	Stack Thermocouple (3)	-
Heated Probe (1)	-	Gasmet Sampling System	-	2m Heated Line (1) (P&G)	-
Heated Probe (2)	CAT 5.111	Bernath 3006 FID	-	1m Heated Line (2)	-
Heated Probe (3)	-	M&C PSS	-	1m Heated Line (3)	-
S-Pitot (1)	CAT 21p166	Mass Flow Controller (1)	-	5m Heated Line (1)	-
S-Pitot (2)	CAT 21S.68	Mass Flow Controller (2)	-	10m Heated Line (1)	-
L-Pitot	-	Mass View (1)	-	20m Heated Line (1)	-
Site Balance	CAT 17.59	Mass View (2)	-	20m Heated Line (2)	-
500g / 1Kg Check Weights	CAT 17.59	Hioki 5043 (V)	-	Dual Channel Heater Controller	-
Last Impinger Arm	-	Hioki 5043 (V)	-	Single Channel Heater Controller	-
Callipers	-	Bioaerosols Temperature Logger	-	Laboratory Balance	CAT 1.18, 1.18a, 1.18b
Tubes Kit Thermocouple	-	Electronic Refrigerator	-	Tape Measure	CAT 16.55

## METHODS & TECHNICAL PROCEDURES USED

Parameter	Standard	Technical Procedure
Total Particulate Matter	EN 13284-1	CAT-TP-01
Water Vapour	EN 14790	CAT-TP-05
Velocity & Vol. Flow Rate	EN 16911-1 (MID)	CAT-TP-41

## PRELIMINARY STACK SURVEY: CALCULATIONS

### General Stack Details

Stack Details (from Traverse)	Units	Value
Stack Diameter / Depth, D	m	1.00
Stack Width, W	m	-
Stack Area, A	m <sup>2</sup>	0.79
Average Stack Gas Temperature, T <sub>a</sub>	°C	31.9
Average Stack Gas Pressure	Pa	85.9
Average Stack Static Pressure, P <sub>static</sub>	kPa	0.030
Average Barometric Pressure, P <sub>b</sub>	kPa	101.2
Average Pitot Tube Calibration Coefficient, C <sub>p</sub>	-	0.85

### Stack Gas Composition & Molecular Weights

Component	Conc ppm	Conc Dry % v/v	Conc Wet % v/v	Volume Fraction r	Molar Mass M	Density kg/m <sup>3</sup> p	Conc kg/m <sup>3</sup> p <sub>i</sub>
CO <sub>2</sub> (Estimated)	-	0.06	0.06	0.0006	44.01	1.9635	0.00118
O <sub>2</sub> (Estimated)	-	20.80	20.70	0.2080	32.00	1.4277	0.29696
N <sub>2</sub>	-	79.14	78.74	0.7914	28.01	1.2498	0.98913
Moisture (H <sub>2</sub> O)	-	-	0.50	0.0050	18.02	0.8037	0.00405

Where:  $p = M / 22.41$

$p_i = r \times p$

### Calculation of Stack Gas Densities

Determinand	Units	Result
Dry Density (STP), P <sub>STD</sub>	kg/m <sup>3</sup>	1.287
Wet Density (STP), P <sub>STW</sub>	kg/m <sup>3</sup>	1.285
Dry Density (Actual), P <sub>Actual</sub>	kg/m <sup>3</sup>	1.152
Average Wet Density (Actual), P <sub>ActualW</sub>	kg/m <sup>3</sup>	1.151

Where: P<sub>STD</sub> = sum of component concentrations, kg/m<sup>3</sup> (not including water vapour)

P<sub>STW</sub> = sum of all wet concentrations / 100 x density, kg/m<sup>3</sup> (including water vapour)

$P_{Actual} = P_{STD} \times (T_{STP} / (P_{STP})) \times ((P_{static} + P_b) / T_a)$

$P_{ActualW}$  (at each sampling point) = P<sub>STW</sub> x (T<sub>s</sub> / P<sub>s</sub>) x (P<sub>a</sub> / T<sub>a</sub>)

### Calculation of Stack Gas Volumetric Flowrate, Q

Duct gas flow conditions	Units	Actual	REF <sup>1</sup>
Temperature	°C	31.9	0.0
Total Pressure	kPa	101.2	101.3
Moisture	%	0.50	0.50

Gas Volumetric Flowrate (from Traverse)	Units	Result
Gas Volumetric Flowrate (Actual)	m <sup>3</sup> /hr	28236
Gas Volumetric Flowrate (STP, Wet)	m <sup>3</sup> /hr	25267
Gas Volumetric Flowrate (STP, Dry)	m <sup>3</sup> /hr	25139
Gas Volumetric Flowrate REF <sup>1</sup>	m <sup>3</sup> /hr	25267

# APPENDIX 2

## PRELIMINARY STACK SURVEY: VELOCITY TRAVERSE TO EN 16911-1 (MID)

(1 of 1)

Parameter	Units	Value
Date of Survey	-	04/07/2019
Time of Survey	-	13:35 - 13:55
Atmospheric Pressure	kPa	101.2
Average Stack Static Pressure	Pa	30
Result of Pitot Stagnation Test	-	Pass
Are Water Droplets Present?	-	No
Device Used	S-Type Pitot with KIMO MP 210 (500Pa)	

Parameter	Units	Value
Initial Pitot Leak Check	-	Pass
Final Pitot Leak Check	-	Pass
Orientation of Duct	-	Vertical
Pitot Tube, $C_p$	-	0.85
Number of Lines Available	-	1
Number of Lines Used	-	1

Sampling Line A						
Traverse Point	Depth m	$\Delta P$ Pa	Temp °C	Wet Density kg/m <sup>3</sup>	Velocity m/s	Swirl °
STATIC (Units: Pa)		30.0				
Mean		85.9	31.9	1.151	9.99	
1	0.03	155.0	36.0	1.134	13.97	40.0
2	0.11	122.0	36.0	1.134	12.40	35.0
3	0.19	84.0	36.0	1.134	10.29	14.0
4	0.32	54.0	3.0	1.270	7.80	10.0
5	0.68	22.0	36.0	1.134	5.26	11.0
6	0.81	45.0	36.0	1.134	7.53	13.0
7	0.90	84.0	36.0	1.134	10.29	43.0
8	0.97	121.0	36.0	1.134	12.35	46.0

# APPENDIX 2

## PRELIMINARY STACK SURVEY: VELOCITY TRAVERSE TO EN 16911-1 (MID) - MEASUREMENT UNCERTAINTY

(1 of 1)

Performance characteristics (Uncertainty Components)	Uncertainty	Value	Units
Standard Uncertainty on the coefficient of the Pitot Tube	$u(k)$	0.005	-
Standard Uncertainty associated with the mean local dynamic pressures	$u(\Delta p_i)$	1.763	Pa
- Resolution	$u(res)$	0.00087	
- Calibration	$u(cal)$	0.768	
- Drift	$u(drift)$	0.083	
- Lack of Fit	$u(fit)$	1.258	
- Overall corrections to dynamic measurements	$u(C_f)$	2.110	
Standard uncertainty associated with the molar mass of the gas	$u(M)$	0.00003	-
- $\phi O_2, w$	-	20.695	
- $\phi CO_2, w$	-	0.060	
- Oxygen, dry	$u(\phi O_2, d)$	0.637	
- Carbon Dioxide, dry	$u(\phi CO_2, d)$	0.002	
- Water Vapour	$u(\phi H_2O)$	0.026	
- Oxygen, wet	$u(\phi O_2, w)$	0.634	
- Carbon Dioxide, wet	$u(\phi CO_2, w)$	0.002	
Standard uncertainty associated with the stack temperature	$u(T_c)$	1.555	K
Standard uncertainty associated with the absolute pressure in the duct	$u(p_c)$	175.701	Pa
- Atmospheric Pressure	$u(p_{atm})$	175.692	
- Static Pressure	$u(p_{stat})$	1.763	
Standard uncertainty associated with the density in the duct	$u(\rho)$	0.00620	-
Standard uncertainty associated with the local velocities	$u(v_i)$	0.136	Pa
Standard uncertainty associated with the mean velocity	$u(\bar{v})$	0.073	m/s
Standard uncertainty associated with the mean velocity (95% Confidence)	$U_c(v)$	0.143	m/s
Standard uncertainty associated with the mean velocity (95% Confidence), relative	$U_{c,rel}(v)$	1.43	%
Standard uncertainty associated with the volume flow rate (95% Confidence)	$U_c(qV, w)$	1340.6	m <sup>3</sup> /hr
- $u^2(a)/a^2$	-	0.00053	
- $u^2(qV, w)/q^2V, w$	-	0.00059	
- $u^2(qV, w)$	-	467843	
- $u(qV, w)$	-	684.0	
Standard uncertainty associated with the volume flow rate (95% Confidence), relative	$U_{c,rel}(qV, w)$	4.75	%

## APPENDIX 2

### TOTAL PARTICULATE MATTER: RESULTS SUMMARY

Sundown Products Ltd, Tilbrook  
S2 - Cooler Plant

#### Sample Runs

Parameter	Units	Run 1		Mean
Concentration	mg/m <sup>3</sup>	26.6		26.6
Uncertainty	±mg/m <sup>3</sup>	2.7		2.7
Mass Emission	g/hr	671		671
Uncertainty	±g/hr	74.9		74.9

Parameter	Units	Run 1		Mean
Water Vapour	% v/v	0.50		0.50
Uncertainty	±% v/v	0.058		0.058

#### Blank Runs

Parameter	Units	Blank 1		Maximum
Concentration	mg/m <sup>3</sup>	0.91		0.91

#### General Sampling Information

Parameter	Value
Standard	EN 13284-1
Technical Procedure	CAT-TP-01
Probe Material	Titanium
Filter Housing Material	Titanium
Positioning of Filter	In Stack
Filter Size and Material	47mm Glass Fibre
Number of Sampling Lines Used	1 / 2
Number of Sampling Points Used	4 / 8
Sample Point I.D.'s	A1 - A8

FORMAT: Number Used / Number Required

FORMAT: Number Used / Number Required

#### Reference Conditions

Reference Conditions are: 273K, 101.3kPa, without correction for water vapour content.

## TOTAL PARTICULATE MATTER: ISOKINETIC SAMPLING CALCULATIONS

Test	Units	Run 1	
<b>Absolute pressure of stack gas, P<sub>s</sub></b>			
Barometric pressure, P <sub>b</sub>	mmHg	759.0	
Stack static pressure, P <sub>static</sub>	mmH <sub>2</sub> O	3.1	
$P_s = (P_b + (P_{static} / 13.6))$	mmHg	759.2	
<b>Volume of water vapour collected, V<sub>wstd</sub></b>			
Total mass collected in impingers (liquid trap)	g	-0.9	
Total mass collected in impingers (silica trap)	g	3.2	
Total mass of liquid collected, V <sub>lc</sub>	g	2.3	
$V_{wstd} = (0.001246)(V_{lc})$	m <sup>3</sup>	0.0029	
<b>Volume of gas metered dry, V<sub>mstd</sub></b>			
Volume of gas sample through gas meter, V <sub>m</sub>	m <sup>3</sup>	0.6060	
Gas meter correction factor, Y <sub>d</sub>	-	1.0290	
Average dry gas meter temperature, T <sub>m</sub>	°C	28.8	
Average pressure drop across orifice, ΔH	mmH <sub>2</sub> O	34.1	
$V_{mstd} = ((0.3592)(V_m)(P_b + (\Delta H/13.6))(Y_d)) / (T_m + 273)$	m <sup>3</sup>	0.5653	
<b>Moisture content, B<sub>w0</sub> &amp; R<sub>wv</sub></b>			
$B_{w0} = V_{wstd} / (V_{mstd} + V_{wstd})$	m <sup>3</sup>	0.0050	
B <sub>w0</sub> as a percentage	% v/v	0.50	
Reported Water Vapour, checked with Tables in EN 14790, R <sub>wv</sub>	% v/v	0.50	
<b>Volume of gas metered wet, V<sub>mstw</sub></b>			
$V_{mstw} = (V_{mstd})(100/(100 - R_{wv}))$	m <sup>3</sup>	0.5681	
<b>Volume of gas metered at Oxygen Reference Conditions, V<sub>mstd@X%O<sub>2</sub></sub> &amp; V<sub>mstw@X%O<sub>2</sub></sub></b>			
IED & Incinerates Hazardous Material? (Yes = no positive O <sub>2</sub> correction)	-	No	
% wet oxygen measured in gas stream, ACT%O <sub>2w</sub>	% v/v	N/A	
% dry oxygen measured in gas stream, ACT%O <sub>2d</sub>	% v/v	N/A	
% oxygen reference condition, REF%O <sub>2</sub>	% v/v	N/A	
O <sub>2</sub> Reference Factor wet (O <sub>2REFw</sub> ) = (21 - REF%O <sub>2</sub> ) / (21 - ACT%O <sub>2w</sub> )	-	N/A	
O <sub>2</sub> Reference Factor dry (O <sub>2REFd</sub> ) = (21 - REF%O <sub>2</sub> ) / (21 - ACT%O <sub>2d</sub> )	-	N/A	
$V_{mstw@X\%oxygen} = (V_{mstw}) / (O_{2REFw})$	m <sup>3</sup>	N/A	
$V_{mstd@X\%oxygen} = (V_{mstd}) / (O_{2REFd})$	m <sup>3</sup>	N/A	
<b>Molecular weight of dry gas stream, M<sub>d</sub></b>			
CO <sub>2</sub> (Estimated)	% v/v	0.06	
O <sub>2</sub> (Estimated)	% v/v	20.80	
Total	% v/v	20.86	
N <sub>2</sub>	% v/v	79.14	
$M_d = 0.44(\%CO_2) + 0.32(\%O_2) + 0.28(\%N_2)$	g/gmol	28.84	
<b>Molecular weight of stack gas (wet), M<sub>s</sub></b>			
$M_s = M_d(1 - (R_{wv}/100)) + 18(R_{wv}/100)$	g/gmol	28.79	
<b>Velocity of stack gas, V<sub>s</sub></b>			
Pitot tube velocity constant, K <sub>p</sub>	-	34.97	
Velocity pressure coefficient, C <sub>p</sub>	-	0.83	
Average of velocity heads, ΔP <sub>avg</sub>	mmH <sub>2</sub> O	10.00	
Average square root of velocity heads, √ΔP	√mmH <sub>2</sub> O	3.16	
Average stack gas temperature, T <sub>s</sub>	°C	38.0	
$V_s = ((K_p)(C_p)(\sqrt{\Delta P})(\sqrt{T_s + 273})) / (\sqrt{M_s}(P_s))$	m/s	10.91	
<b>Total flow of stack gas: Actual (Q<sub>a</sub>), Wet (Q<sub>stw</sub>), Dry (Q<sub>std</sub>), Wet@O<sub>2REF</sub> (Q<sub>stwO<sub>2</sub></sub>), Dry@O<sub>2REF</sub> (Q<sub>stdO<sub>2</sub></sub>)</b>			
Area of stack, A <sub>s</sub>	m <sup>2</sup>	0.79	
$Q_a = (60)(A_s)(V_s)$	m <sup>3</sup> /min	514.2	
Conversion factor (K/mm.Hg), C <sub>f</sub>	-	0.3592	
$Q_{stw} = ((Q_a)(P_s)(C_f)) / ((T_s) + 273)$	m <sup>3</sup> /min	450.9	
$Q_{std} = ((Q_a)(P_s)(C_f)(1 - (R_{wv}/100))) / ((T_s) + 273)$	m <sup>3</sup> /min	448.6	
$Q_{stwO_2} = ((Q_a)(P_s)(C_f)) / ((T_s) + 273) / (O_{2REFw})$	m <sup>3</sup> /min	N/A	
$Q_{stdO_2} = ((Q_a)(P_s)(C_f)(1 - (R_{wv}/100))) / ((T_s) + 273) / (O_{2REFd})$	m <sup>3</sup> /min	N/A	
<b>Percent isokinetic, %I</b>			
Nozzle diameter, D <sub>n</sub>	mm	6.01	
Nozzle area, A <sub>n</sub>	mm <sup>2</sup>	28.37	
Total sampling time, q	min	32	
$\%I = (4.6398E^6)(T_s + 273)(V_{mstd}) / (P_s)(V_s)(A_n)(q)(1 - (R_{wv}/100))$	%	109.0	



## TOTAL PARTICULATE MATTER: SAMPLING DETAILS

### Sample Runs

Parameter	Units	Run 1
Sampling Times	-	14:00 - 14:32
Sampling Dates	-	04/07/2019
Sampling Device	-	ISO
Volume Sampled (REF)	m <sup>3</sup>	0.5681
Filter I.D. Number	-	47-62799
Start Filter Mass	g	0.14620
End Filter Mass	g	0.15377
Total Mass on Filter	g	0.00757
Probe Rinse I.D. Number	-	PR-47-62799
Start Probe Rinse Mass	g	2.96216
End Probe Rinse Mass	g	2.96968
Total Mass in Probe Rinse	g	0.00752
Total Mass Collected	mg	15.09
Calculated Concentration	mg/m <sup>3</sup>	26.56
Balance Uncertainty / LOD	mg/m <sup>3</sup>	0.30

**Where:** ISO stands for Manual Isokinetic Sampling Train

### Blank Runs

Parameter	Units	Blank 1
Blank Dates	-	04/07/2019
Average Volume Sampled (REF)	m <sup>3</sup>	0.5681
Filter I.D. Number	-	47-62800
Start Filter Mass	g	0.14807
End Filter Mass	g	0.14822
Total Mass on Filter	g	0.00015
Probe Rinse I.D. Number	-	PR-47-62800
Start Probe Rinse Mass	g	3.02664
End Probe Rinse Mass	g	3.02701
Total Mass in Probe Rinse	g	0.00037
Total Mass Collected	mg	0.52
Calculated Concentration	mg/m <sup>3</sup>	0.91
Balance Uncertainty / LOD	mg/m <sup>3</sup>	0.30

# TOTAL PARTICULATE MATTER: QUALITY ASSURANCE

(PAGE 1 OF 2)

## Sample Runs

Leak Test Results	Units	Run 1	
Mean Sampling Rate	l/min	19.5	
Pre-Sampling Leak Rate	l/min	0.20	
Post-Sampling Leak Rate	l/min		
Allowable Leak Rate	l/min	0.36	
Leak Test Acceptable	-	Yes	
Water Droplets	Units	Run 1	
Are Water Droplets Present	-	No	
MU (Concurrent Water Vapour)	Units	Run 1	
Measurement Uncertainty (MU)	%	11.4	
Allowable MU	%	20.0	
MU Acceptable	%	Yes	
Silica Gel (Concurrent Water Vapour)	Units	Run 1	
Less than 50% Faded	%	Yes	
Isokinetic Criterion Compliance	Units	Run 1	
Isokinetic Variation	%	109.0	
Allowable Isokinetic Range	%	95 - 115	
Isokineticity Acceptable	-	Yes	
Weighing Uncertainty Criteria	Units	Run 1	
Overall Weighing Uncertainty	± mg	0.32	
Overall Weighing Uncertainty	± mg/m <sup>3</sup>	0.56	
ELV [Daily ELV for IED]	mg/m <sup>3</sup>	150.00	
Allowable Weighing Uncertainty	mg/m <sup>3</sup>	7.50	
Weighing Uncertainty Acceptable	-	Yes	
Filter Temperatures	Units	Run 1	
Pre-Conditioning Temperature	°C	180	
Post-Conditioning Temperature	°C	160	
Maximum Filter Temperature	°C	38	
Test Conditions	Units	Run 1	
Ambient Temperature Recorded?	-	Yes	

## APPENDIX 2

### TOTAL PARTICULATE MATTER: QUALITY ASSURANCE

(PAGE 2 OF 2)

#### Blank Runs

Leak Test Results	Units	Blank 1	
Expected Sampling Rate	l/min	19.0	
Pre-Sampling Leak Rate	l/min	0.20	
Post-Sampling Leak Rate	l/min		
Allowable Leak Rate	l/min	0.38	
Leak Test Acceptable	-	Yes	

Validity of Blank vs ELV	Units	Blank 1	
Allowable Blank	mg/m <sup>3</sup>	15.0	
Blank Acceptable	-	Yes	

Acetone / Water Rinse Blank	Units	Blank
Acetone / Water Rinse Value	mg/l	2.7
Allowable Blank	mg/l	10
Blank Acceptable	-	Yes

#### Method Deviations

Nature of Deviation	Run Number	
(x = deviation applies to the associated run, wx = deviation also applies to the concurrent water vapour run)	1	
Only one out of two required sampling lines was available, however the number of sample points used on the available line were increased to the minimum required by the Standard	x	
The sample points where the angle of swirl was > 15° were omitted from the sampling exercise. The effective number of points was doubled and any non-compliant swirl points after this increase were omitted.	x	

## TOTAL PARTICULATE MATTER: MEASUREMENT UNCERTAINTY CALCULATIONS

Measured Quantities	Value		Standard uncertainty		
	Symbol	Run 1	Symbol	Units	Run 1
Sampled Volume (Actual)	V <sub>m</sub>	0.6060	uV <sub>m</sub>	m <sup>3</sup>	0.0121
Sampled Gas Temperature	T <sub>m</sub>	301.8	uT <sub>m</sub>	K	2.0
Sampled Gas Pressure	p <sub>m</sub>	101.2	up <sub>m</sub>	kPa	0.5
Sampled Gas Humidity	H <sub>m</sub>	0.0	uH <sub>m</sub>	% v/v	1.0
Leak	L	1.03	uL	%	-
Mass of Particulate	m	15.09	um	mg	0.17
Uncollected Mass	UCM	0.52	uUCM	mg	-

Measured Quantities	Uncertainty as a Percentage		Requirement of Standard
	Units	Run 1	
Sampled Volume (Actual)	%	2.00	≤2%
Sampled Gas Temperature	%	0.66	≤1%
Sampled Gas Pressure	%	0.49	≤1%
Sampled Gas Humidity	%	1.00	≤1%
Leak	%	1.03	≤2%
Mass of Particulate	%	0.20	<5% of ELV
Uncollected Mass	%	-	-

Measured Quantities	Uncertainty in Measurement Units			Sensitivity Coefficient	
	Symbol	Units	Run 1	Run 1	
Sampled Volume (STP)	V <sub>m</sub>	m <sup>3</sup>	0.5653	46.99	
Leak	L	mg/m <sup>3</sup>	0.157	1.00	
Mass of Particulate	L <sub>r</sub>	mg	15.090	1.76	
Uncollected Mass	UCM	mg	0.30	1.76	

Measured Quantities	Uncertainty in Result	
	Units	Run 1
Sampled Volume (STP)	mg/m <sup>3</sup>	0.666
Leak	mg/m <sup>3</sup>	0.1574
Mass of Particulate	mg/m <sup>3</sup>	0.2992
Uncollected Mass	mg/m <sup>3</sup>	0.5250

Measured Quantities	Oxygen Correction Part of MU Budget	
	Units	Run 1
O <sub>2</sub> Correction Factor	-	N/A
Stack Gas O <sub>2</sub> Content	% v/v	N/A
MU for O <sub>2</sub> Correction	-	N/A
Overall MU For O <sub>2</sub> Measurement	%	N/A

Parameter	Units	Run 1
Combined uncertainty	mg/m <sup>3</sup>	0.91
Expanded uncertainty (95% confidence), without Oxygen Correction	mg/m <sup>3</sup>	1.79
Expanded uncertainty (95% confidence), with Oxygen Correction	mg/m <sup>3</sup>	N/A
Expanded uncertainty (95% confidence), estimated with Method Deviations	mg/m <sup>3</sup>	2.68
Reported Uncertainty	mg/m <sup>3</sup>	2.68
Expanded uncertainty (95% confidence), without Oxygen Correction	%	6.7
Expanded uncertainty (95% confidence), with Oxygen Correction	%	N/A
Expanded uncertainty (95% confidence), estimated with Method Deviations	%	10.1
Reported Uncertainty	%	10.1