



Unit 11, Aspen Close, Swindon, SN2 8AJ  
 T: 0800 328 1821  
 E: stuart.davidson@cat-env.com  
 Your Catalyst Contact: Stuart Davidson (07957 554 956)

**Stack Emissions Testing Report Commissioned by**  
 PCME Ltd

**Installation Name & Address**

Clark-Drain Ltd  
 Station Road  
 Yaxley  
 Peterborough  
 Cambridgeshire  
 PE7 3EG

EPR Permit: A12/92; Variation: PPC 20/09

**Stack Reference**  
 Galvanising Plant

**Dates of the Monitoring Campaign**  
 6th November 2012


**Job Reference Number**  
 CSW-0962

<b>Report Written by</b>
Andrew Matthews Team Leader MCERTS Level 2 MM 09 1026 TE1 TE3 TE4

<b>Report Approved by</b>
Paul Martin Team Leader MCERTS Level 2 MM 04 503 TE1 TE2 TE3 TE4

<b>Report Date</b>
15th November 2012

<b>Version</b>
Version 1

<b>Signature of Report Approver</b>


## CONTENTS

TITLE PAGE	
CONTENTS	2
EXECUTIVE SUMMARY	
Monitoring Objectives	3
Monitoring Results	4
Monitoring Dates & Times	5
Process Details	6
Monitoring & Analytical Methods	7
Summary of Method Deviations	7
Sampling Location	8
Plant Photos / Sample Points	9
APPENDIX 1 - Monitoring Personnel & List of Equipment	
APPENDIX 2 - Raw Data, Sampling Equations & Charts	
APPENDIX 3 - PCME Meter	

*Opinions and interpretations expressed herein are outside the scope of Catalyst Environmental Ltd's UKAS accreditation.*

*This test report shall not be reproduced, except in full, without the written approval of Catalyst Environmental Ltd.*

## Executive Summary

(Page 1 of 7)

### MONITORING OBJECTIVES

Clark-Drain Ltd, Yaxley  
Galvanising Plant  
6th November 2012

#### Overall Aim of the Monitoring Campaign

Catalyst Environmental Ltd, in partnership with PCME Ltd, were commissioned to carry out stack emissions testing on the Galvanising Plant by Clark-Drain Ltd at Yaxley.

The aim of the monitoring campaign was to conduct stack emissions testing as part of PCME's calibration service in support of the PCME particulate monitor installed at the emissions point.

#### Special Requirements

Record the PCME Meter readings. These can be found on the back page of this Report.

#### Target Parameters

Total Particulate Matter

## Executive Summary

(Page 2 of 7)

### MONITORING RESULTS

Clark-Drain Ltd, Yaxley  
Galvanising Plant  
6th November 2012

Parameter	Concentration				Mass Emission			
	Units	Result	MU +/-	Limit	Units	Result	MU +/-	Limit
Total Particulate Matter	<sup>1</sup> mg/m <sup>3</sup>	10.5	0.55	15	g/hr	80.9	4.2	-
Water Vapour	% v/v	2.1	0.10					
Stack Gas Temperature	°C	22.8						
Stack Gas Velocity	m/s	5.7						
Volumetric Flow Rate (ACTUAL)	m <sup>3</sup> /hr	8334						
Volumetric Flow Rate (REF)	<sup>1</sup> m <sup>3</sup> /hr	7715						

NOTE: VOLUMETRIC FLOW RATE DATA TAKEN FROM THE PRELIMINARY VELOCITY TRAVERSE.

<sup>1</sup> Reference Conditions (REF) are: 273K, 101.3kPa, without correction for water vapour content.

## Executive Summary

(Page 3 of 7)

### MONITORING DATE(S) & TIMES

Clark-Drain Ltd, Yaxley  
Galvanising Plant  
6th November 2012

Parameter	Units	Concentration	Units	Mass Emission	Sampling Date(s)	Sampling Times	Duration mins	
Total Particulate Matter	R1	mg/m <sup>3</sup>	9.5	g/hr	73.0	06/11/2012	10:28 - 11:28	60
Total Particulate Matter	R2	mg/m <sup>3</sup>	8.9	g/hr	68.8	06/11/2012	11:55 - 12:55	60
Total Particulate Matter	R3	mg/m <sup>3</sup>	13.1	g/hr	100.8	06/11/2012	13:17 - 14:17	60
Velocity & Volumetric Flow Rate	R1					06/11/2012	09:15 - 09:30	

All results are expressed at the respective reference conditions.

## Executive Summary

(Page 4 of 7)

### PROCESS DETAILS

Clark-Drain Ltd, Yaxley  
Galvanising Plant  
6th November 2012

#### Standard Operating Conditions

Parameter	Value
Process Status	Normal
Capacity (of 100%) and Tonnes / Hour	Various
Continuous or Batch Process	Batch
Feedstock (if applicable)	Steel Components
Abatement System	Wet Scrubber
Abatement System Running Status	On
Fuel	N/A
Plume Appearance	No Plume Visible

## Executive Summary

(Page 5 of 7)

### MONITORING & ANALYTICAL METHODS

Clark-Drain Ltd, Yaxley  
Galvanising Plant  
6th November 2012

Parameter	Monitoring				Analysis				MCERTS Testing	LOD (Average)
	Standard	Technical Procedure	UKAS Testing	Testing Lab	Analytical Procedure	Analytical Technique	UKAS Analysis	Analysis Lab		
Total Particulate Matter	BS EN 13284-1	CAT-TP-01	Yes	CAT	CAT-TP-03	Gravimetric	Yes	CAT	Yes	0.11 mg/m <sup>3</sup>
Water Vapour	BS EN 14790	CAT-TP-05	Yes	CAT	CAT-TP-05	Gravimetric	Yes	CAT	Yes	0.1 % v/v
Velocity & Vol. Flow Rate	BS EN 13284-1	CAT-TP-04	Yes	CAT	Pitot Tube and Thermocouple				Yes	N/A

### ANALYSIS LABORATORIES

(with short name reference as appears in the table above)

Catalyst Environmental Ltd (CAT)	UKAS Accreditation Number: 4279
----------------------------------	---------------------------------

### SUMMARY OF SAMPLING DEVIATIONS

Parameter	Run	Deviation
Total Particulate Matter	All	One out of two sampling lines was used due to sampling location restrictions, however the number of sample points used on the available line were increased to meet the requirements of the Standard.

## Executive Summary

(Page 6 of 7)

### SUITABILITY OF SAMPLING LOCATION

#### Duct Characteristics

Parameter	Units	Value
Type	-	Circular
Depth	m	0.72
Width	m	-
Area	m <sup>2</sup>	0.41
Port Depth	cm	9
Orientation of Duct	-	Vertical
Sample Port Size	-	4" BSP

#### Location of Sampling Platform

General Platform Information	Value
Permanent / Temporary Platform	Permanent
Inside / Outside	Outside

#### Platform Details

EA Technical Guidance Note M1 / BS EN 15259 Platform Requirements	Value
Sufficient working area to manipulate probe and operate the measuring instruments	Yes
Platform has 2 levels of handrails (approx. 0.5m & 1.0m high)	Yes
Platform has vertical base boards (approx. 0.25m high)	Yes
Platform has chains / self closing gates at top of ladders	No
There are no obstructions present which hamper insertion of sampling equipment	Yes
Safe Access Available	Yes
Easy Access Available	Yes

#### Sampling Location / Platform Improvement Recommendations

All platforms should be designed in accordance with the requirements in the Environment Agency's Technical Guidance Note M1 and BS EN 15259.

#### BS EN 15259 Homogeneity Test Requirements

There is no requirement to perform a BS EN 15259 Homogeneity Test on this Stack.

#### Sampling Plane Validation Criteria (from EA Technical Guidance Document (Monitoring) M1)

Criteria in M1	Units	Traverse 1	Required	Compliant
Lowest Differential Pressure	Pa	10.0	> 5 Pa	Yes
Mean Velocity	m/s	5.68	-	-
Lowest Gas Velocity	m/s	3.52	-	-
Highest Gas Velocity	m/s	7.04	-	-
Ratio of Above	: 1	2.00	< 3 : 1	Yes
Maximum Angle of Swirl	°	6	< 15°	Yes
No Local Negative Flow	-	Yes	-	Yes



# Executive Summary

(Page 7 of 7)

## PLANT PHOTOS

Photo 1



Photo 2




Photo 3



Photo 4



## SAMPLE POINTS



**where** ○ = isokinetic point sampled at  
 ● = isokinetic point not sampled at

APPENDICES

**APPENDIX CONTENTS**

APPENDIX 1 - Stack Emissions Monitoring Personnel, List of Equipment & Methods and Technical Procedures Used

APPENDIX 2 - Summaries, Calculations, Raw Data and Charts

APPENDIX 3 - PCME Meter

APPENDIX 1

**STACK EMISSIONS MONITORING PERSONNEL**

Position	Name	MCERTS Accreditation	MCERTS Number	Technical Endorsements
Team Leader	Andrew Matthews	MCERTS Level 2	MM 09 1026	TE1 TE3 TE4
Technician	Wayne Rossouw	MCERTS Level 1	MM 10 1083	None

**LIST OF EQUIPMENT**

Extractive Sampling		Instrumental Analysers		Miscellaneous Items	
Equipment Type	Equipment I.D.	Equipment Type	Equipment I.D.	Equipment Type	Equipment I.D.
Control Box DGM	CAT 7.22	Horiba PG-250	-	Digital Manometer (1)	CAT 3.77
Box Thermocouples	CAT 3.61	Servomex 4900	-	Digital Manometer (2)	-
Umbilical	CAT 3.61	Eco Physics CLD 822Mh	-	Digital Temperature Meter	CAT 3.77
Oven Box	-	Testo 350 XL	-	Stopwatch	CAT 14.42
Probe	CAT 5.63	Servomex 5200MP	-	Barometer	CAT 13.5
S-Pitot (1)	CAT 21S.33	JCT JCC P1 Cooler	-	Stack Thermocouple (1)	CAT 4.259
S-Pitot (2)	CAT 21P.39	FT-IR	-	Stack Thermocouple (2)	CAT 4.306
L-Pitot	-	FT-IR Sampling System	-	1m Heated Line (1)	-
500g Check Weight	CAT 17.17	Bernath 3006 FID	-	1m Heated Line (2)	-
1Kg Check Weight	CAT 17.17	Heated Head Filter	-	1m Heated Line (3)	-
Last Impinger Arm	-	Mass Flow Controller (1)	-	5m Heated Line (1)	-
Callipers	CAT 23.20	Mass Flow Controller (2)	-	15m Heated Line (1)	-
Tubes Kit Thermocouple	-	Mass View (1)	-	15m Heated Line (2)	-
Laboratory Balance	CAT 1.18	Mass View (2)	-	20m Heated Line (1)	-
Tape Measure	CAT 16.29	Easylogger EN-EL-12 Bit	-	Dual Channel Heater Controller	-

**METHODS & TECHNICAL PROCEDURES USED**

Parameter	Standard	Technical Procedure
Total Particulate Matter	BS EN 13284-1	CAT-TP-01
Water Vapour	BS EN 14790	CAT-TP-05
Velocity & Vol. Flow Rate	BS EN 13284-1	CAT-TP-04

## PRELIMINARY STACK SURVEY: CALCULATIONS

### General Stack Details

Stack Details (from Traverse)	Units	Value
Stack Diameter / Depth, D	m	0.72
Stack Width, W	m	-
Stack Area, A	m <sup>2</sup>	0.41
Average Stack Gas Temperature, T <sub>a</sub>	°C	22.8
Average Stack Gas Pressure	Pa	26.9
Average Stack Static Pressure, P <sub>static</sub>	kPa	0.029
Average Barometric Pressure, P <sub>b</sub>	kPa	101.6
Average Pitot Tube Calibration Coefficient, C <sub>p</sub>	-	0.86

### Stack Gas Composition & Molecular Weights

Component	Conc ppm	Conc Dry % v/v	Conc Wet % v/v	Volume Fraction r	Molar Mass M	Density kg/m <sup>3</sup> p	Conc kg/m <sup>3</sup> p <sub>i</sub>
CO <sub>2</sub> (Estimated)	-	0.06	0.06	0.0006	44.01	1.9635	0.00118
O <sub>2</sub> (Estimated)	-	20.8	20.4	0.2080	32.00	1.4277	0.29696
N <sub>2</sub>	-	79.1	77.5	0.7914	28.01	1.2498	0.98913
Moisture (H <sub>2</sub> O)	-	-	2.1	0.0210	18.02	0.8037	0.01685

Where:  $p = M / 22.41$   
 $p_i = r \times p$

### Calculation of Stack Gas Densities

Determinand	Units	Result
Dry Density (STP), P <sub>STD</sub>	kg/m <sup>3</sup>	1.29
Wet Density (STP), P <sub>STW</sub>	kg/m <sup>3</sup>	1.28
Dry Density (Actual), P <sub>Actual</sub>	kg/m <sup>3</sup>	1.19
Average Wet Density (Actual), P <sub>ActualW</sub>	kg/m <sup>3</sup>	1.18

Where:  $P_{STD}$  = sum of component concentrations, kg/m<sup>3</sup> (not including water vapour)  
 $P_{STW}$  = sum of all wet concentrations / 100 x density, kg/m<sup>3</sup> (including water vapour)  
 $P_{Actual} = P_{STD} \times (T_{STP} / (P_{STP})) \times ((P_{static} + P_b) / T_a)$   
 $P_{ActualW}$  (at each sampling point) =  $P_{STW} \times (T_s / P_s) \times (P_a / T_a)$

### Calculation of Stack Gas Volumetric Flowrate, Q

Duct gas flow conditions	Units	Actual	REF <sup>1</sup>
Temperature	°C	22.8	0.0
Total Pressure	kPa	101.6	101.3
Moisture	%	2.10	2.10

Gas Volumetric Flowrate (from Traverse)	Units	Result
Gas Volumetric Flowrate (Actual)	m <sup>3</sup> /hr	8334
Gas Volumetric Flowrate (STP, Wet)	m <sup>3</sup> /hr	7715
Gas Volumetric Flowrate (STP, Dry)	m <sup>3</sup> /hr	7554
Gas Volumetric Flowrate REF <sup>1</sup>	m <sup>3</sup> /hr	7715

APPENDIX 2

**PRELIMINARY STACK SURVEY: VELOCITY TRAVERSE**

(1 of 1)

Parameter	Units	Value
Date of Survey	-	06/11/2012
Time of Survey	-	09:15 - 09:30
Atmospheric Pressure	kPa	101.6
Stack Static Pressure	Pa	29
Type of Pitot Used	-	S-Type Pitot
Are Water Droplets Present?	-	No

Parameter	Units	Value
Initial Pitot Leak Check	-	Pass
Final Pitot Leak Check	-	Pass
Orientation of Duct	-	Vertical
Pitot Tube, C <sub>p</sub>	-	0.86
Number of Lines Available	-	2
Number of Lines Used	-	1

Swirl Point (taken at the sampling points used during testing)																				
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20
Angle of Swirl (°)	1	2	5	6																

Traverse Point	Depth m	ΔP	Sampling Line A - Cap Stuck			Sampling Line B			
			Temp °C	Wet Density kg/m <sup>3</sup>	Velocity m/s	ΔP Pa	Temp °C	Wet Density kg/m <sup>3</sup>	Velocity m/s
1	0.04					10.0	22.5	1.184	3.52
2	0.11					18.0	22.5	1.184	4.72
3	0.18					28.0	22.6	1.183	5.88
4	0.25					35.0	22.6	1.183	6.58
5	0.32					22.0	22.8	1.183	5.22
6	0.40					33.0	22.9	1.182	6.39
7	0.47					29.0	23.0	1.182	5.99
8	0.54					40.0	23.0	1.182	7.04
9	0.61					32.0	23.2	1.181	6.30
10	0.68					22.0	23.2	1.181	5.22
<b>Mean</b>						<b>26.9</b>	<b>22.8</b>	<b>1.182</b>	<b>5.68</b>

**TOTAL PARTICULATE MATTER: RESULTS SUMMARY**

Clark-Drain Ltd, Yaxley  
Galvanising Plant

**Sample Runs**

Parameter	Units	Run 1	Run 2	Run 3		Mean
Concentration	mg/m <sup>3</sup>	9.46	8.92	13.07		10.48
Uncertainty	±mg/m <sup>3</sup>	0.50	0.48	0.67		0.55
Mass Emission	g/hr	73.0	68.8	100.8		80.9
Uncertainty	±g/hr	3.9	3.7	5.2		4.2

Parameter	Units	Run 1	Run 2	Run 3		Mean
Water Vapour	% v/v	2.2	2.1	2.0		2.1
Uncertainty	±% v/v	0.11	0.10	0.10		0.10

**Blank Runs**

Parameter	Units	Blank 1		Maximum
Concentration	mg/m <sup>3</sup>	0.11		0.11

NOTE: Where the Balance Uncertainty / Limit of Detection is higher than the Blank concentration, the Balance Uncertainty / Limit of Detection concentration has been reported.

**General Sampling Information**

Parameter	Value	
Standard	BS EN 13284-1	
Technical Procedure	CAT-TP-01	
Probe Material	Titanium	
Filter Housing Material	Titanium	
Positioning of Filter	In Stack	
Filter Size and Material	47mm Quartz Fibre	
Number of Sampling Lines Used	1 / 2	FORMAT: Number Used / Number Required
Number of Sampling Points Used	4 / 4	FORMAT: Number Used / Number Required
Sample Point I.D.'s	B1, B2, B3, B4	

**Reference Conditions**

Reference Conditions are: 273K, 101.3kPa, without correction for water vapour content.

APPENDIX 2

**TOTAL PARTICULATE MATTER: ISOKINETIC SAMPLING CALCULATIONS**

Test	Units	Run 1	Run 2	Run 3	
<b>Absolute pressure of stack gas, P<sub>s</sub></b>					
Barometric pressure, P <sub>b</sub>	mmHg	762.0	762.0	762.0	
Stack static pressure, P <sub>static</sub>	mmH <sub>2</sub> O	3.0	3.0	3.0	
P <sub>s</sub> = (P <sub>b</sub> + (P <sub>static</sub> / 13.6))	mmHg	762.2	762.2	762.2	
<b>Volume of water vapour collected, V<sub>wstd</sub></b>					
Total mass collected in impingers (liquid trap)	g	17.7	18.8	19.6	
Total mass collected in impingers (silica trap)	g	12.7	9.3	5.9	
Total mass of liquid collected, V <sub>lc</sub>	g	30.4	28.1	25.5	
V <sub>wstd</sub> = (0.001246)(V <sub>lc</sub> )	m <sup>3</sup>	0.0379	0.0350	0.0318	
<b>Volume of gas metered dry, V<sub>mstd</sub></b>					
Volume of gas sample through gas meter, V <sub>m</sub>	m <sup>3</sup>	1.7040	1.7110	1.5960	
Gas meter correction factor, Y <sub>d</sub>	-	1.0210	1.0210	1.0210	
Average dry gas meter temperature, T <sub>m</sub>	°C	14.7	15.9	18.3	
Average pressure drop across orifice, ΔH	mmH <sub>2</sub> O	90.0	91.4	79.9	
V <sub>mstd</sub> = ((0.3592)(V <sub>m</sub> (P <sub>b</sub> + (ΔH/13.6))(Y <sub>d</sub> )) / (T <sub>m</sub> + 273))	m <sup>3</sup>	1.6698	1.6696	1.5428	
<b>Moisture content, B<sub>wo</sub> &amp; R<sub>wv</sub></b>					
B <sub>wo</sub> = V <sub>wstd</sub> / (V <sub>mstd</sub> + V <sub>wstd</sub> )	m <sup>3</sup>	0.0222	0.0205	0.0202	
B <sub>wo</sub> as a percentage	% v/v	2.22	2.05	2.02	
Reported Water Vapour, checked with Tables in BS EN 14790, R <sub>wv</sub>	% v/v	2.22	2.05	2.02	
<b>Volume of gas metered wet, V<sub>mstw</sub></b>					
V <sub>mstw</sub> = (V <sub>mstd</sub> )(100/(100 - R <sub>wv</sub> ))	m <sup>3</sup>	1.7076	1.7046	1.5745	
<b>Volume of gas metered at Oxygen Reference Conditions, V<sub>mstd@X%O<sub>2</sub></sub> &amp; V<sub>mstw@X%O<sub>2</sub></sub></b>					
WID & Incinerates Hazardous Material? (Yes = no positive O <sub>2</sub> correction)	-	No	No	No	
% wet oxygen measured in gas stream, ACT%O <sub>2w</sub>	% v/v	N/A	N/A	N/A	
% dry oxygen measured in gas stream, ACT%O <sub>2d</sub>	% v/v	N/A	N/A	N/A	
% oxygen reference condition, REF%O <sub>2</sub>	% v/v	N/A	N/A	N/A	
O <sub>2</sub> Reference Factor wet (O <sub>2REFw</sub> ) = (21 - REF%O <sub>2</sub> ) / (21 - ACT%O <sub>2w</sub> )	-	N/A	N/A	N/A	
O <sub>2</sub> Reference Factor dry (O <sub>2REFd</sub> ) = (21 - REF%O <sub>2</sub> ) / (21 - ACT%O <sub>2d</sub> )	-	N/A	N/A	N/A	
V <sub>mstw@X%oxygen</sub> = (V <sub>mstw</sub> ) / (O <sub>2REFw</sub> )	m <sup>3</sup>	N/A	N/A	N/A	
V <sub>mstd@X%oxygen</sub> = (V <sub>mstd</sub> ) / (O <sub>2REFd</sub> )	m <sup>3</sup>	N/A	N/A	N/A	
<b>Molecular weight of dry gas stream, M<sub>d</sub></b>					
CO <sub>2</sub> (Estimated)	% v/v	0.06	0.06	0.06	
O <sub>2</sub> (Estimated)	% v/v	20.80	20.80	20.80	
Total	% v/v	20.86	20.86	20.86	
N <sub>2</sub>	% v/v	79.14	79.14	79.14	
M <sub>d</sub> = 0.44(%CO <sub>2</sub> )+0.32(%O <sub>2</sub> )+0.28(%N <sub>2</sub> )	g/gmol	28.84	28.84	28.84	
<b>Molecular weight of stack gas (wet), M<sub>s</sub></b>					
M <sub>s</sub> = M <sub>d</sub> (1 - (R <sub>wv</sub> /100)) + 18(R <sub>wv</sub> /100)	g/gmol	28.60	28.62	28.62	
<b>Velocity of stack gas, V<sub>s</sub></b>					
Pitot tube velocity constant, K <sub>p</sub>	-	34.97	34.97	34.97	
Velocity pressure coefficient, C <sub>p</sub>	-	0.83	0.83	0.83	
Average of velocity heads, ΔP <sub>avg</sub>	mmH <sub>2</sub> O	3.77	3.63	3.17	
Average square root of velocity heads, √ΔP	vmmH <sub>2</sub> O	1.94	1.90	1.78	
Average stack gas temperature, T <sub>s</sub>	°C	23.3	23.3	25.5	
V <sub>s</sub> = ((K <sub>p</sub> )(C <sub>p</sub> )(√ΔP)(√T <sub>s</sub> + 273)) / (√(M <sub>s</sub> )(P <sub>s</sub> ))	m/s	6.60	6.47	6.07	
<b>Total flow of stack gas: Actual (Q<sub>a</sub>), Wet (Q<sub>stw</sub>), Dry (Q<sub>std</sub>), Wet@O<sub>2REF</sub> (Q<sub>stwO<sub>2</sub></sub>), Dry@O<sub>2REF</sub> (Q<sub>stdO<sub>2</sub></sub>)</b>					
Area of stack, A <sub>s</sub>	m <sup>2</sup>	0.41	0.41	0.41	
Q <sub>a</sub> = (60)(A <sub>s</sub> )(V <sub>s</sub> )	m <sup>3</sup> /min	161.3	158.1	148.3	
Conversion factor (K/mm.Hg), C <sub>f</sub>	-	0.3592	0.3592	0.3592	
Q <sub>stw</sub> = ((Q <sub>a</sub> )(P <sub>s</sub> )(C <sub>f</sub> )) / ((T <sub>s</sub> + 273))	m <sup>3</sup> /min	149.1	146.1	136.0	
Q <sub>std</sub> = ((Q <sub>a</sub> )(P <sub>s</sub> )(C <sub>f</sub> )(1 - (R <sub>wv</sub> /100))) / ((T <sub>s</sub> + 273))	m <sup>3</sup> /min	145.7	143.1	133.3	
Q <sub>stwO<sub>2</sub></sub> = ((Q <sub>a</sub> )(P <sub>s</sub> )(C <sub>f</sub> )) / ((T <sub>s</sub> + 273)(O <sub>2REFw</sub> )	m <sup>3</sup> /min	N/A	N/A	N/A	
Q <sub>stdO<sub>2</sub></sub> = ((Q <sub>a</sub> )(P <sub>s</sub> )(C <sub>f</sub> )(1 - (R <sub>wv</sub> /100))) / ((T <sub>s</sub> + 273)(O <sub>2REFd</sub> )	m <sup>3</sup> /min	N/A	N/A	N/A	
<b>Percent isokinetic, %I</b>					
Nozzle diameter, D <sub>n</sub>	mm	9.84	9.84	9.84	
Nozzle area, A <sub>n</sub>	mm <sup>2</sup>	76.06	76.06	76.06	
Total sampling time, q	min	60	60	60	
%I = (4.6398E <sup>6</sup> )(T <sub>s</sub> +273)(V <sub>mstd</sub> ) / (P <sub>s</sub> )(V <sub>s</sub> )(A <sub>n</sub> )(q)(1 - (R <sub>wv</sub> /100))	%	102.2	104.1	103.3	

**TOTAL PARTICULATE MATTER: SAMPLING DETAILS**

**Sample Runs**

Parameter	Units	Run 1	Run 2	Run 3	
Sampling Times	-	10:28 - 11:28	11:55 - 12:55	13:17 - 14:17	
Sampling Dates	-	06/11/2012	06/11/2012	06/11/2012	
Sampling Device	-	ISO	ISO	ISO	
Volume Sampled (REF)	m <sup>3</sup>	1.7076	1.7046	1.5745	
Filter I.D. Number	-	47-10735	47-10743	47-10821	
Start Filter Mass	g	0.15730	0.15501	0.15609	
End Filter Mass	g	0.17302	0.16967	0.17630	
Total Mass on Filter	g	0.01572	0.01466	0.02021	
Probe Rinse I.D. Number	-	PR-47-10735	PR-47-10743	PR-47-10821	
Start Probe Rinse Mass	g	3.05465	3.12870	2.95481	
End Probe Rinse Mass	g	3.05509	3.12925	2.95518	
Total Mass in Probe Rinse	g	0.00044	0.00055	0.00037	
Total Mass Collected	mg	16.16	15.21	20.58	
Calculated Concentration	mg/m <sup>3</sup>	9.46	8.92	13.07	
Balance Uncertainty / LOD	mg/m <sup>3</sup>	0.11	0.11	0.11	

**Where:** ISO stands for Manual Isokinetic Sampling Train

**Blank Runs**

Parameter	Units	Blank 1	
Blank Dates	-	06/11/2012	
Average Volume Sampled (REF)	m <sup>3</sup>	1.6623	
Filter I.D. Number	-	47-10630	
Start Filter Mass	g	0.15517	
End Filter Mass	g	0.15521	
Total Mass on Filter	g	0.00004	
Probe Rinse I.D. Number	-	PR-47-10630	
Start Probe Rinse Mass	g	2.91384	
End Probe Rinse Mass	g	2.91389	
Total Mass in Probe Rinse	g	0.00005	
Total Mass Collected	mg	0.09	
Calculated Concentration	mg/m <sup>3</sup>	0.05	
Balance Uncertainty / LOD	mg/m <sup>3</sup>	0.11	



APPENDIX 2

**TOTAL PARTICULATE MATTER: QUALITY ASSURANCE**

(PAGE 1 OF 2)

**Sample Runs**

<b>Leak Test Results</b>	<b>Units</b>	<b>Run 1</b>	<b>Run 2</b>	<b>Run 3</b>	
Mean Sampling Rate	l/min	29.00	29.12	27.16	
Pre-Sampling Leak Rate	l/min	0.13	0.09	0.08	
Post-Sampling Leak Rate	l/min	0.06	0.06	0.07	
Allowable Leak Rate	l/min	0.58	0.58	0.54	
Leak Test Acceptable	-	Yes	Yes	Yes	

<b>Water Droplets</b>	<b>Units</b>	<b>Run 1</b>	<b>Run 2</b>	<b>Run 3</b>	
Are Water Droplets Present	-	No	No	No	

<b>MU (Concurrent Water Vapour)</b>	<b>Units</b>	<b>Run 1</b>	<b>Run 2</b>	<b>Run 3</b>	
Measurement Uncertainty (MU)	%	4.9	4.9	4.9	
Allowable MU	%	20	20	20	
MU Acceptable	%	Yes	Yes	Yes	

<b>Silica Gel (Concurrent Water Vapour)</b>	<b>Units</b>	<b>Run 1</b>	<b>Run 2</b>	<b>Run 3</b>	
Less than 50% Faded	%	Yes	Yes	Yes	

<b>Isokinetic Criterion Compliance</b>	<b>Units</b>	<b>Run 1</b>	<b>Run 2</b>	<b>Run 3</b>	
Isokinetic Variation	%	102.2	104.1	103.3	
Allowable Isokinetic Range	%	95 - 115	95 - 115	95 - 115	
Isokineticity Acceptable	-	Yes	Yes	Yes	

<b>Weighing Uncertainty Criteria</b>	<b>Units</b>	<b>Run 1</b>	<b>Run 2</b>	<b>Run 3</b>	
Overall Weighing Uncertainty	± mg	0.31	0.31	0.31	
Overall Weighing Uncertainty	± mg/m <sup>3</sup>	0.18	0.18	0.20	
ELV [Daily ELV for WID]	mg/m <sup>3</sup>	15.00	15.00	15.00	
Allowable Weighing Uncertainty	mg/m <sup>3</sup>	0.75	0.75	0.75	
Weighing Uncertainty Acceptable	-	Yes	Yes	Yes	

<b>Filter Temperatures</b>	<b>Units</b>	<b>Run 1</b>	<b>Run 2</b>	<b>Run 3</b>	
Pre-Conditioning Temperature	°C	180	180	180	
Post-Conditioning Temperature	°C	160	160	160	
Maximum Filter Temperature	°C	23	23	26	

<b>Test Conditions</b>	<b>Units</b>	<b>Run 1</b>	<b>Run 2</b>	<b>Run 3</b>	
Ambient Temperature Recorded?	-	Yes	Yes	Yes	

**TOTAL PARTICULATE MATTER: QUALITY ASSURANCE**

(PAGE 2 OF 2)

**Blank Runs**

Leak Test Results	Units	Blank 1	
Expected Sampling Rate	l/min	18.00	
Pre-Sampling Leak Rate	l/min	0.11	
Post-Sampling Leak Rate	l/min	0.12	
Allowable Leak Rate	l/min	0.36	
Leak Test Acceptable	-	Yes	

Validity of Blank vs ELV	Units	Blank 1	
Allowable Blank	mg/m <sup>3</sup>	1.5	
Blank Acceptable	-	Yes	

Acetone / Water Rinse Blank	Units	Blank
Acetone / Water Rinse Value	mg/l	2.7
Allowable Blank	mg/l	10
Blank Acceptable	-	Yes

**Method Deviations**

Nature of Deviation	Run Number			
	1	2	3	
(x = deviation applies to the associated run, wx = deviation also applies to the concurrent water vapour run)				
One out of two sampling lines was used due to sampling location restrictions, however the number of sample points used on the available line were increased to meet the requirements of the Standard.	wx	wx	wx	

APPENDIX 2

**TOTAL PARTICULATE MATTER: MEASUREMENT UNCERTAINTY CALCULATIONS**

Measured Quantities	Value				Standard uncertainty				
	Symbol	Run 1	Run 2	Run 3	Symbol	Units	Run 1	Run 2	Run 3
Sampled Volume (Actual)	V <sub>m</sub>	1.7040	1.7110	1.5960	uV <sub>m</sub>	m <sup>3</sup>	0.0341	0.0342	0.0319
Sampled Gas Temperature	T <sub>m</sub>	287.7	288.9	291.3	uT <sub>m</sub>	K	2.0	2.0	2.0
Sampled Gas Pressure	p <sub>m</sub>	101.6	101.6	101.6	up <sub>m</sub>	kPa	0.5	0.5	0.5
Sampled Gas Humidity	H <sub>m</sub>	0.0	0.0	0.0	uH <sub>m</sub>	% v/v	1.0	1.0	1.0
Leak	L	0.21	0.21	0.26	uL	%	-	-	-
Mass of Particulate	m	16.16	15.21	20.58	um	mg	0.18	0.18	0.18
Oxygen Content	O <sub>2,m</sub>	N/A	N/A	N/A	uO <sub>2,m</sub>	% v/v	N/A	N/A	N/A
Uncollected Mass	UCM	0.09	0.09	0.09	uUCM	mg	-	-	-

Measured Quantities	Uncertainty as a Percentage				Requirement of Standard
	Units	Run 1	Run 2	Run 3	
Sampled Volume (Actual)	%	2.00	2.00	2.00	≤2%
Sampled Gas Temperature	%	0.70	0.69	0.69	≤1%
Sampled Gas Pressure	%	0.49	0.49	0.49	≤1%
Sampled Gas Humidity	%	1.00	1.00	1.00	≤1%
Leak	%	0.21	0.21	0.26	≤2%
Mass of Particulate	%	0.70	0.70	0.76	<5% of ELV
Oxygen Content	%	N/A	N/A	N/A	≤5%
Uncollected Mass	%	-	-	-	-

Measured Quantities	Uncertainty in Measurement Units					Sensitivity Coefficient		
	Symbol	Units	Run 1	Run 2	Run 3	Run 1	Run 2	Run 3
Sampled Volume (STP)	V <sub>m</sub>	m <sup>3</sup>	1.6698	1.6696	1.5428	5.67	5.34	8.47
Leak	L	mg/m <sup>3</sup>	0.011	0.011	0.019	1.00	1.00	1.00
Mass of Particulate	L <sub>r</sub>	mg	16.160	15.207	20.580	0.59	0.59	0.64
Factor for O <sub>2</sub> Correction	O <sub>2,m</sub>	% v/v	N/A	N/A	N/A	N/A	N/A	N/A
Uncollected Mass	UCM	mg	0.05	0.05	0.05	0.59	0.59	0.64

Measured Quantities	Uncertainty in Result			
	Units	Run 1	Run 2	Run 3
Sampled Volume (STP)	mg/m <sup>3</sup>	0.230	0.217	0.320
Leak	mg/m <sup>3</sup>	0.0113	0.0106	0.0195
Mass of Particulate	mg/m <sup>3</sup>	0.1054	0.1056	0.1143
Factor for O <sub>2</sub> Correction	mg/m <sup>3</sup>	N/A	N/A	N/A
Uncollected Mass	mg/m <sup>3</sup>	0.0304	0.0305	0.0330

Parameter	Units	Run 1	Run 2	Run 3
Combined uncertainty	mg/m <sup>3</sup>	0.25	0.24	0.34
Expanded uncertainty (95% confidence)	mg/m <sup>3</sup>	0.50	0.48	0.67
Expanded uncertainty (95% confidence), estimated with Method Deviations	mg/m <sup>3</sup>	0.50	0.48	0.67
Reported Uncertainty	mg/m <sup>3</sup>	0.50	0.48	0.67
Expanded uncertainty (95% confidence)	%	5.3	5.4	5.1
Expanded uncertainty (95% confidence), estimated with Method Deviations	%	5.3	5.4	5.1
Reported Uncertainty	%	5.3	5.4	5.1

APPENDIX 3

PCME METER

Contract Details	
Test House Job Number	CSW-0962
Company	Clark-Drain Ltd
Site	Yaxley
Stack	Galvanising Plant
Sampling Date	06/11/2012
PCME Job Number	J32913373

Stack Conditions	Value	Units
Stack Temperature	24.1	°C
Stack Humidity	2.1	% v/v
Stack Oxygen Content	N/A	% v/v
Stack Pressure	101.6	kPa

Current Instrument Settings	Type	Serial Number
Controller Type	IM	34304
Channel Type	DT 373	34803
Channel Number	1	
Instrument Checks	Pass	
Current Calibration Factor	4.76	
Time on Display	10:24	
Time Difference - Meter v Actual	PCME meter is 40 mins fast	
GMT / BST?	GMT	
Was Time Changed?	No	

Hardware Status	
Zero	2
Span	10027
S/C	10035
Contamination Ring	Pass
Comms Check	Pass

Summary of Test Data - Results of SRM vs CEM									
Run	Start Time	Finish Time	Instrument Average	Instrument Maximum	TPM Conc. STP WET	TPM Conc. STP DRY	TPM Conc. STP WET, % O <sub>2</sub>	TPM Conc. STP DRY, % O <sub>2</sub>	TPM Conc. ACTUAL
1	10:28	11:28	4.41	36.88	9.46	9.68	N/A	N/A	8.72
2	11:55	12:55	3.25	5.10	8.92	9.11	N/A	N/A	8.22
3	13:17	14:17	3.79	7.81	13.07	13.34	N/A	N/A	12.05
<b>Mean</b>			<b>3.82</b>		<b>10.48</b>	<b>10.71</b>	<b>N/A</b>	<b>N/A</b>	<b>9.67</b>

For all matters relating to the function, performance and calibration of the PCME Meter, please speak directly to PCME on 01480 468 200.

Times listed in the table above relate to the actual time of the tests, and not the times as read by the PCME meter.