Environmental emissions monitoring

Vironmental Report Ref: 17-00829

Date: February 2017

Workplace air monitoring

Workplace noise monitoring

Environmental noise monitoring

HAVS

Indoor air quality

Biological agents

Hazmat survevs

COSHH assessments

Training

LEV



EMISSIONS MONITORING TO COMPLY WITH HUNTINGDON DISTRICT COUNCIL PERMIT B04/94

Linx Printing Technologies, 33 Edison Road, St Ives ("Unit 4")

Report Written by: Simon Skentelbery

info@ssuk.eu 01782 341827

CONTENTS

| | EXECUTIVE SUMMARY | 3 |
|----|-------------------|---|
| 1. | INTRODUCTION | 4 |
| 2. | PROCEDURES | 4 |
| 3. | OBSERVATIONS | 4 |
| 4. | RESULTS | 4 |
| 5. | CONCLUSIONS | 4 |

EXECUTIVE SUMMARY

Emissions to atmosphere were assessed on the 22nd February 2017 at "Unit 4" Linx Printing Technologies, to assess the levels of VOC and particulate matter being emitted from the stacks fed by the Local Exhaust Ventilation (LEV). The results and information obtained during the visit indicated that all results were found to be below the limits stated in Huntingdonshire Council Permit B04/94

SURVEYED BY:

VERIFIED BY:

Simon Skentelbery General Manager Matthew Wadie Principal Consultant

Industrial Safety Solutions undertake site and process confidentiality relating to your business at all times. If you have any queries regarding this report contact Industrial Safety Solutions – MH2 Building, Parkhall Business Village, Parkhall Road, Stoke on Trent, ST3 5XA.

1. INTRODUCTION

On 22nd February 2017 emissions monitoring was completed on behalf of Mr James Barnes at Linx Printing Technologies, Edison Road, St Ives (known as Unit 4) was completed by Simon Skentelbery. The monitoring was carried out to assess emissions of VOC and total particulate matter being emitted into the atmosphere from the Main Stack of the Local Exhaust Ventilation (LEV) systems.

2. PROCEDURES

MCERTS were not requested and are not applicable to the work detailed in this report.

3. OBSERVATIONS

Stack velocity was measured using a pitot tube, coupled to an electronic manometer, both are calibrated annually by a UKAS accredited supplier. Temperature measurements were taken using a K-type thermocouple connected to an electronic thermometer, again both are calibrated annually by a UKAS accredited supplier.

The Main Stack serves all LEV systems within the Ink Production plant.

Production levels were considered to be normal.

4. RESULTS

4.1 Particulate Matter

| Run No. | Sampling Time | Total Particulate | Concentration (mg/m³) | Local Authority Limit (mg/m³) |
|-----------|---------------|-------------------|-----------------------|----------------------------------|
| 1 | 08:51-09:51 | 1.18 | 0.63 | 20mg/m³ 8 hour mean |
| 2 | 09:56-10:56 | 0.98 | 0.54 | |
| 3 | 11:01-12:01 | 1.22 | 0.60 | |
| 4 | 12:07-13:07 | 0.99 | 0.48 | |
| 5 | 13:12-14:12 | 1.18 | 0.56 | |
| 6 | 14:15-15:15 | 1.17 | 0.52 | |
| 7 | 15:19-16:19 | 0.99 | 0.47 | |
| 8 | 16:19-17:19 | 1.33 | 0.64 | |
| 8-hour me | ean | 0.55 | | |

4.1 VOC

| | Concentration | Emission | Local Authority |
|---------------|---------------|--------------|----------------------|
| Sampling Time | (mg/m³) | Rate*(kg/hr) | Limit (mg/m³) |
| 09:26-17:15 | 34.4 | 0.11 | 150mg.m ³ |

^{*}Based on volumetric flowrate of 0.91m³/sec

5. **CONCLUSIONS**

The results and information obtained during the visit indicated that all results were found to be below the limits stated in Huntingdonshire Council Permit B04/94